







Key

- ① Existing deck/substrate prepared and primed in strict accordance with LIQUIFLEX Project Specification
- ②  PROVAP S/A Vapour Control Layer (where required) applied in strict accordance with LIQUIFLEX Project Specification
- ③  PIR Insulation bonded in strict accordance with LIQUIFLEX Project Specification
- ④  PROVAP S/A Carrier Membrane applied in strict accordance with LIQUIFLEX Project Specification
- ⑤  LIQUIFLEX-PRO fully reinforced with LIQUIMAT glass fibre matting applied in strict accordance with LIQUIFLEX Project Specification
- ⑥  LIQUITOP applied in strict accordance with LIQUIFLEX Project Specification
- ⑦ Minimum 18mm thick exterior grade plywood fixed to parapet, prepared and primed
- ⑧  Type-C Decotrim mechanically fixed with specified LIQUIFLEX PRO fixings or fully bonded with specified LIQUIFLEX PRO Adhesive

