







Key

- ① New 18mm thick plywood laid on top of existing timber deck.
- ②  **PROVAP S/A Vapour Control Layer** (where required) applied in strict accordance with **LIQUIFLEX** Project Specification
- ③  **PIR Insulation** bonded in strict accordance with **LIQUIFLEX** Project Specification
- ④  **PROVAP S/A Carrier Membrane** applied in strict accordance with **LIQUIFLEX** Project Specification
- ⑤  **LIQUIFLEX-PRO** fully reinforced with **LIQUIMAT** glass fibre matting applied in strict accordance with **LIQUIFLEX** Project Specification
- ⑥  **LIQUITOP** applied in strict accordance with **LIQUIFLEX** Project Specification
- Ⓐ  **PROVAP Primer** applied at **all** positions shown in strict accordance with **LIQUIFLEX** Plastics Project Specification

