

Key

- ① Existing deck/substrate prepared and primed in strict accordance with **LIQUIFLEX** Project Specification
- ② **PROVAP S/A Vapour Control Layer** (where required) applied in strict accordance with **LIQUIFLEX** Project Specification
- ③ **PIR Insulation** bonded in strict accordance with **LIQUIFLEX** Project Specification
- ④ **PROVAP S/A Carrier Membrane** applied in strict accordance with **LIQUIFLEX** Project Specification
- ⑤ **LIQUIFLEX-PRO** fully reinforced with **LIQUIMAT** glass fibre matting applied in strict accordance with **LIQUIFLEX** Project Specification
- ⑥ **LIQUITOP** applied in strict accordance with **LIQUIFLEX** Project Specification
- ⑦ Temporary masking tape applied to the cured **LIQUIFLEX** applied **LIQUITOP** to demarcate the proposed walkway
- ⑧ Contrasting colour of **LIQUITOP** applied as a 'tack coat' at 0.25l/m²
- ⑨ **Skid Inhibiting Grit** broadcast in to the wet 'tack coat' of contrasting Top Coat [Item No. 8] @ 3.0kg/m², and allowed to dry, remove all surplus unbonded grit with clean brushes etc. and providing it remains uncontaminated, the grit can be stored for re-use.
- ⑩ **LIQUITOP** applied at 0.25l/m² – colour Green

