

Key

- ① Existing deck/substrate prepared and primed in strict accordance with **LIQUIFLEX** Project Specification
- ② **PROVAP S/A Vapour Control Layer** (where required) applied in strict accordance with **LIQUIFLEX** Project Specification
- ③ **PIR Insulation** bonded in strict accordance with **LIQUIFLEX** Project Specification
- ④ **PROVAP S/A Carrier Membrane** applied in strict accordance with **LIQUIFLEX** Project Specification
- ⑤ **LIQUIFLEX-PRO** fully reinforced with **LIQUIMAT** glass fibre matting applied in strict accordance with **LIQUIFLEX PRO** Project Specification
- ⑥ **LIQUITOP** applied in strict accordance with **LIQUIFLEX** Project Specification
- ⑦ **LIQUIFLEX** Applied Membrane terminated with a mechanically fixed **LIQUIFLEX PRO** Termination Bar, sealed and bedded with specific **LIQUIFLEX PRO** sealant

